

5/24

DART AEROSPACE LTD	Work Order:	23579
Description: Plug	Part Number:	D2651-1
11 03.12.19		
Drawing: D2651 Rev.A+B	Qty:	500

Step	Location	Procedure	By	Date	Qty
1	EXPEDITING	Open W/O	JH	05.06.16	500
2	CNC CELL	Machine as per folio FA219 Material: 6061-T6(QQ-A-225/8) or equivalent. .500" Dia Batch <u>116491</u> M13466	J.G	05/06/16	500
3	QC	Inspect level 2	J.G	05/06/20	500
4	QC	Inspect level 8	FL	05-06-22	500
5	METAL	Deburr <i>and tumbler</i>	ml	05-06-27	495 PTO
6	QC	Inspect Level 5	J	05-07-04	454 PTO
7	FINISHING	Acid etch and alodine per QSI 005 4.1	ML	05 07 04	495
8	FINISHING	Powder coat gloss white (Ref: 4.3.5.1) per QSI 005 4.3 (Only larger section necessary)	FL	05 08 02	495
9	STORES	Identify and Stock	FL	05 08 02	495
10	EXPEDITING	Close W/O Inspect level 21 Cost / Part .70 <i>595 05/08/10</i> (495)	LS	05/08/10	485

Rev	Date	Change	Revised By	Approved
A	02.04.15	New Issue	NG	<i>02-04-15</i>

RELEASED

02/04/15

W/O:		WORK ORDER CHANGES					
DATE	STEP	PROCEDURE CHANGE	By	Date	Qty	Approval Mfg / Design Mgr	Approval QC Inspector

NCR: 23579		WORK ORDER NON-CONFORMANCE (NCR)						
DATE	STEP	Description of NC Section A	Corrective Action Section B			Verification Section C	Approval Design Mgr	Approval QC Inspector
			Initial Design Mgr	Action Description Design Mgr	Sign & Date			
05.06.20	2/3	Total length of plug is 0.009 over tol. (0.394"), are parts acceptable Qty 500	CP 05.06.20	Acceptable this time	[Signature] 05.06.20	[Signature] 05.06.20	CP 05.06.21 per QSR 692	[Signature] 05.06.20
05-06-27	5	Find the box done. We have to re-do the steps	[Signature] 05-06-27	No Body sign the step. I re-do because there No Good and I sign	[Signature] 05-06-27	[Signature] 05-06-27	[Signature] 05-06-27	[Signature] 05-06-27
05-07-04	6	1 Plug found too short by 0.045 [Sketch]	[Signature] 05-07-04	Scrap	[Signature] 05-07-04	[Signature] 05-07-04	[Signature] 05-07-04	[Signature] 05-07-04

Part No: _____ PAR #: _____ Fault Category: _____ NCR: Yes ☐ No ☒ DQA: ☒ Date: 05/08/02

NOTE: Date & initial all entries

QA: N/C Closed: _____ Date: _____




DESIGN <i>[Signature]</i>	DRAWN BY <i>[Signature]</i>	DART AEROSPACE LTD HAWKESBURY, ONTARIO, CANADA	
CHECKED <i>[Signature]</i>	APPROVED <i>[Signature]</i>	DRAWING NO. D2651	REV. B SHEET 1 OF 1
DATE 03.12.19		TITLE PLUG	SCALE 1:1
A	97.03.25	NEW ISSUE	
B	03.12.19	ADD POWDER COAT, MS28775-008	


RELEASED

03.12.19 *[Signature]*

D2651-1 PLUG:



GROOVE DETAIL (SCALE 5:1)



D2651-1 PLUG

- 1) MATERIAL: 6061-T6 (QQ-A-225/8) OR 1100-0 (QQ-A-225/1)
- 2) FINISH: ACID ETCH & ALODINE PER DART QSI 005 4.1
POWDER COAT WHITE (4.3.5.1) PER DART QSI 005 4.3
- 3) TOLERANCES ARE PER DART QSI 018 UNLESS OTHERWISE NOTED
- 4) ALL DIMENSIONS ARE IN INCHES
- 5) BREAK ALL SHARP EDGES 0.010 MAX

D2651-3 O-RING

- 1) MATERIAL: BUNA N, 70 DUROMETER
3/16 ID, 5/16 OD, 1/16 WIDTH
(PARKER 2-008, MS28775-008 OR EQUIVALENT)

SMOKE COPY
RETURN TO
ENGINEERING
UNCONTROLLED COPY
SUBJECT TO AMENDMENT
WITHOUT NOTICE

WORK ORDER
NO. 23579

Copyright © 1997 by DART AEROSPACE LTD

THIS DOCUMENT IS PRIVATE AND CONFIDENTIAL AND IS SUPPLIED ON THE EXPRESS CONDITION THAT IT IS NOT TO BE USED FOR ANY PURPOSE OR COPIED OR COMMUNICATED TO ANY OTHER PERSON WITHOUT WRITTEN PERMISSION FROM DART AEROSPACE LTD.

Job Costing Report

Dart Aerospace Ltd.
Hawkesbury

Jun 16, 2005
08:04 am

Work Order No : 0023579
Project Name : D2651-1
Project For : WK524
Work Order Type : Main
Main WO Number :
House Part Number : D2651-1
Description : Plug
Manufactured : Yes
Amount Req'd : 500
Amount Done : 0
Start Date : 06-15-05
Est Finish Date : 06-24-05
Act Finish Date :
Drawings Req'd : No
Ok for Approval :
Approval Rec'd :

Department Code:
Burden Flags : NNNNNNNN
WO Status : Open
Invoice State : Not Invoiced
Invoice Date :
Invoice Number :
Invoice Amount : 0.00
Order Entry No :
OE Value : 0.00
Est Mark Up : 0.000%
Actual Mark Up : 0.000%
\$0 Posted to Finished Goods

	Estimated	Actual	Var. %	Posted	To Post
Material Cost :	0.00	0.00	0.00	0.00	0.00
Engineering Hours :	0.00	0.00	0.00		
Engineering Cost :	0.00	0.00	0.00	0.00	0.00
Production Hours :	0.00	0.00	0.00		
Production Cost :	0.00	0.00	0.00	0.00	0.00
Packaging Hours :	0.00	0.00	0.00		
Packaging Cost :	0.00	0.00	0.00	0.00	0.00
OverHead Hours :	0.00	0.00	0.00		
OverHead Cost :	0.00	0.00	0.00	0.00	0.00
CNC Hours :	0.00	0.00	0.00		
CNC :	0.00	0.00	0.00	0.00	0.00
Misc. Hours :	0.00	0.00	0.00		
Misc. :	0.00	0.00	0.00	0.00	0.00
Burden :	0.00	0.00	0.00		
Total Cost :	0.00	0.00	0.00		
Mark up :	0.000	0.000			
Selling Cost :	0.00	0.00			

	Estimated	Actual
Labour Hrs/Amount Done :	0.00	0.00
Profits/(Loss) :	0.00	0.00

Chris Provencal

From: "David Shepherd" <davids@dartaero.com>
To: "Chris Provencal" <chrisp@dartaero.com>
Sent: June 21, 2005 12:24 PM
Subject: Re: D2651-1 plug problem

0.394 is acceptable

----- Original Message -----

From: Chris Provencal
To: David Shepherd
Sent: Monday, June 20, 2005 1:08 PM
Subject: D2651-1 plug problem

D2651-1 plug (ie the o-ring plug for the 206 skid tubes), The parts are over tolerance by 0.009" (0.394") on the 0.375" dimension. Dan indicated that from his experience this shouldn't be a problem. I will send a fax of the dwg.

Sincerely,

Chris Provencal

***DART* Aerospace Ltd.**

Email...chrisp@dartaero.com

Phone...613-632-3336

Fax.....613-632-4443

21/06/2005